BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT29413

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2018-19, Date: 01.08.2018

Beautification of Indira Canteen Site in ward 07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEP SURAPARAJU ( )	
				In Figures	In Words
1	59.4	KSRRB 300-1 Earthwork excavation by manual means in ordinary soil involiving an avarage horizontal throw upto 2 meters and an avarage lift upto 1.50m excavated surface leveled and sides neatly defssed, the disposed earth to be leveled neatly after breaking of clods comlete asspecifications.(page no141, item no19.1)	Cum	81.1	Rupees Eighty One and Ten Paise Only
2	99.33	KSRRB 300-1 Earthwork excavation by manual means in ordinary soil involiving an avarage horizontal throw upto 2 meters and an avarage lift upto 1.50m excavated surface leveled and sides neatly defssed, the disposed earth to be leveled neatly after breaking of clods comlete asspecifications.(page no141, item no19.1)	Cum	4990.39	Rupees Four Thousand Nine Hundred Ninety and Thirty Nine Paise Only
3	31.68	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23 / Item No. 34.8.2,	Cum	4140.86	Rupees Four Thousand One Hundred Forty and Eighty Six Paise Only
4	18.77	Providing and constructing granite/trap/basalt size stone masonry in basement with cement mortar 1: 6 stone chistel dressed in courses not less than 15 cms high bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications (item no.5.9, page no.23)	Cum	4949.84	Rupees Four Thousand Nine Hundred Forty Nine and Eighty Four Paise Only
5	4.35	Providing and laying in position plain cement concret of mix 1:2:4 with cement @ 240kgs with 20mm and down size graded granite metal coarse agregates @ 0.69cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exeeding 15 cm thick well compacted in foundation and plinth and cills, including cost all materilas, labour, HOM of machinery, curing complete as per specifications (page no.12 , I,no-4.6)	Cum	5381.04	Rupees Five Thousand Three Hundred Eighty One and Four Paise Only
6	52	KSRB 5-11 : Providing and constructing non load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 Page No. 25 / Item No. 5.28,	Sqm	926.67	Rupees Nine Hundred Twenty Six and Sixty Seven Paise Only
7	52	KSRB 15.3.1 Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No.113 / Item No.15.9, PWD SR 2016-17	Sqm	179.01	Rupees One Hundred Seventy Nine and One Paise Only
8	60	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Cum	1959.3	Rupees One Thousand Nine Hundred Fifty Nine and Thirty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

27/09